MIRAMAR
SHOPPING CENTER

MIRAMAR SHOPPING CENTER
2000 HIGHWAY 146 • SEABROOK, TX 77586

SIGN PACKAGE

State of Texas Electrical Sign Contractor
License Number: 18967
Regulated by the Texas Department of Licensing and Regulation
P.O. Box 12157, Austin TX 78711
Telephone (512) 463-6599; Toll Free (in Texas): (800) 803-9202
Online - http://www.license.state.tx.us/Complaints

You may also make a note that if your company cannot resolve an issue, the customer has a right to complain to the TDLR

SIGNCOAMERICA



Code allowance is:

- 1 sign every 500' – 12' OAH – max sign width is 24' and height 10' - max square footage is 80.
- Setback is minimum 5' from property lines.
- The sign base and sign structure for a monument sign shall be brick, stone, or masonry material matching the front facade of the building.
- The sign face shall be framed by a minimum of six inches of brick, stone, or masonry material matching the front facade of the building.
- The monument base shall be a maximum of two feet in height and shall be included in the calculation of total height.
- For multi-tenant developments, the development name, if included as an integral part of the monument structure (i.e., not a separate panel), will not count toward the maximum sign face area as long as the area of the development name does not exceed 20 percent of the allowable maximum sign face area.

5 YEAR WARRANTY
ALL PARTS. ALL LABOR.
OUR PROMISE.

PAINT COLORS

- P1: Off White - Exact color to be provided by sales **– with stucco finish**
- P2: MP 80489 **– with stucco finish**
- P3: SW 2835 Craftsman Brown **– with stucco finish**

Approved by: _____

M1 Masonry – Exact specification to be provided to Signco America

M2 Masonry – Modular Brick – painted P3

SIGNCOAMERICA
7938 WRIGHT RD • HOUSTON, TX 77041 • 713-661-1500
www.SigncoAmerica.com

CLIENT	MIRAMAR SHOPPING CENTER	**DRAWING**	SCA18 2545 O:\14-PROJECTS\M	**REVISIONS**		**APPROVALS**	
ADDRESS	2000 HIGHWAY 146	**DESIGNER**	OUN	**R6**	4.15.2020 - ADD 3RD OPTION - OUN	**CLIENT**	
CITY/ STATE	SEABROOK, TX 77586	**SALES REP**	GLORIA BAKER	**R7**	5.18.2020 - CHANGE SIZES, COLORS - OUN	**LANDLORD**	
DATE	5.22.19	**PROJECT MGR**	PATTY HICKS	**R8**	5.29.2020 - OPTION 2 = 31'	**SALES REP**	

SPECIFICATIONS ALL ELECTRIC SIGNS AND PRODUCTS MANUFACTURED BY SIGNCO AMERICA ARE BUILT ACCORDING TO **UL** STANDARDS

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

THIS DRAWING IS THE PROPERTY OF SIGNCOAMERICA, LP. ANY REPRODUCTION OR EXHIBITION OF THIS DRAWING IS STRICTLY PROHIBITED. © 2020 ALL RIGHTS RESERVED

SIGN A 31' – REJECTED — QTY: 2

FABRICATE AND INSTALL DOUBLE FACED ILLUMINATED MONUMENT SIGNS

Crowns:
- All aluminum construction, Finish P1

ID Section:
- Aluminum construction, Finish P2
- Graphics: Routed into face and backed w/ ¾" White Acrylic #2447, ⅜" to extend past face
- Illuminated using white LEDs by GE

Top Tenant Section:
- Aluminum construction Finish P2
- Faces: white flex faces

Tenant graphics: Cast / Printed vinyl as per tenant requirements
Printed vinyl = 3 year warranty
Tenant graphics are included at time of install only
Typical graphics shown, Final Tenant graphics are to be provided to Signco America prior to
fabrication in print / cut ready forma
- Illuminated using white LEDs

t

Pole Covers
- Aluminum construction Finish P3

Address
- ⅜" white Acrylic
- Mounting: Flush Stud-mounted on pole cover (street side)

Concrete Pads: 3" Above & 3" Below Grade

Accents:
- 2'' x 2'' Aluminum Square tube frame Finish P1

APPROVED BY PLANNING & ZONING 10-2019
REJECTED BY CITY COUNCIL 11-2019





END VIEW

5 YEAR WARRANTY
ALL PARTS. ALL LABOR.
OUR PROMISE.

SIGN DETAILS
SCALE: ¼" = 1'-0"

SIGNCOAMERICA
7938 WRIGHT RD • HOUSTON, TX 77041 • 713-661-1500
www.SigncoAmerica.com

CLIENT	MIRAMAR SHOPPING CENTER	**DRAWING**	SCA18 2545 O:\14-PROJECTS\M	**REVISIONS**		**APPROVALS**	
ADDRESS	2000 HIGHWAY 146	**DESIGNER**	OUN	**R6**	4.15.2020 - ADD 3RD OPTION - OUN	**CLIENT**	
CITY/ STATE	SEABROOK, TX 77586	**SALES REP**	GLORIA BAKER	**R7**	5.18.2020 - CHANGE SIZES, COLORS - OUN	**LANDLORD**	
DATE	5.22.19	**PROJECT MGR**	PATTY HICKS	**R8**	5.29.2020 - OPTION 2 = 31'	**SALES REP**	

NEW CONSTRUCTION T/R **PAGE 3**

SPECIFICATIONS ALL ELECTRIC SIGNS AND PRODUCTS MANUFACTURED BY SIGNCO AMERICA ARE BUILT ACCORDING TO **UL** STANDARDS

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

THIS DRAWING IS THE PROPERTY OF SIGNCOAMERICA, LP. ANY REPRODUCTION OR EXHIBITION OF THIS DRAWING IS STRICTLY PROHIBITED. © 2020 ALL RIGHTS RESERVED

SIGN A 22' – PROPOSED — QTY: 2

FABRICATE AND INSTALL DOUBLE FACED ILLUMINATED MONUMENT SIGNS

Ⓐ Cap: all aluminum construction, painted P1

Ⓑ ID / Tenant section:
Aluminum frame with durock: M2 masonry applied to durock
Masonry supplied and installed by Signco America

ID panel: aluminum painted P2
ID graphics: Routed into face and backed w/ ¾" White Acrylic #2447, ⅜" to extend past face

Tenant section: 2" aluminum retainers and 2½" aluminum divider bars painted P2
Tenant faces: 3/16" 7328 white acrylic
Tenant graphics: Cast / Printed vinyl as per tenant requirements
Printed vinyl = 3 year warranty
Tenant graphics are included at time of install only
Typical graphics shown, Final Tenant graphics are to be provided to Signco America prior to
fabrication in print / cut ready format

Illuminated using white LEDs by GE

Ⓒ Pole covers: all aluminum construction, painted P3 with caps painted P1

Aluminum reveal painted P1

Pole cover base: Aluminum frame with durock
M1 masonry applied to durock
Masonry supplied and installed by Signco America

Address on street facing end: 3/8" thick acrylic painted P3, flush mounted

Concrete Pad: 3" Above & 3" Below Grade

Support / Foundation as per engineering requirements

See page 2 for paint and masonry specifications





SIGN DETAILS
SCALE: 3/8" = 1'-0"

END VIEW

SIGNCOAMERICA
7938 WRIGHT RD • HOUSTON, TX 77041 • 713-661-1500
www.SigncoAmerica.com

CLIENT	MIRAMAR SHOPPING CENTER	DRAWING	SCA18 2545 O:\14-PROJECTS\M	REVISIONS		APPROVALS	
ADDRESS	2000 HIGHWAY 146	DESIGNER	OUN	R6	4.15.2020 - ADD 3RD OPTION - OUN	CLIENT	
CITY/ STATE	SEABROOK, TX 77586	SALES REP	GLORIA BAKER	R7	5.18.2020 - CHANGE SIZES, COLORS - OUN	LANDLORD	
DATE	5.22.19	PROJECT MGR	PATTY HICKS	R8	5.29.2020 - OPTION 2 = 31'	SALES REP	

NEW CONSTRUCTION VIP PAGE 4

SPECIFICATIONS ALL ELECTRIC SIGNS AND PRODUCTS MANUFACTURED BY SIGNCO AMERICA ARE BUILT ACCORDING TO **UL** STANDARDS

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

THIS DRAWING IS THE PROPERTY OF SIGNCOAMERICA, LP. ANY REPRODUCTION OR EXHIBITION OF THIS DRAWING IS STRICTLY PROHIBITED. © 2020 ALL RIGHTS RESERVED

SIGN A 12' – PER CODE — QTY: 2

FABRICATE AND INSTALL DOUBLE FACED ILLUMINATED MONUMENT SIGNS

Ⓐ Cap: all aluminum construction, painted P1

Ⓑ ID / Tenant section:
Aluminum frame with durock: M2 masonry applied to durock
Masonry supplied and installed by Signco America

Address on street facing end: 3/8" thick acrylic
painted P3, flush mounted

ID and tenant sections project 2" from masonry

ID panel: aluminum painted P2
ID graphics: Routed into face and backed w/ ¾" White Acrylic #2447, ⅜" to extend past face

Tenant section: 1½" aluminum retainers and 1½" aluminum divider bars painted P2
Tenant faces: 3/16" 7328 white acrylic
Tenant graphics: Cast / Printed vinyl as per tenant requirements
Printed vinyl = 3 year warranty
Tenant graphics are included at time of install only
Typical graphics shown, Final Tenant graphics are to be provided to Signco America prior to
fabrication in print / cut ready format

Illuminated using white LEDs by GE

Ⓒ Base: aluminum reveal painted P1

Base: Aluminum frame with durock – M1 masonry applied to durock
Masonry supplied and installed by Signco America

Concrete Pad: 3" Above & 3" Below Grade

Support / Foundation as per engineering requirements

See page 2 for paint and masonry specifications





END VIEW

5 YEAR WARRANTY
ALL PARTS. ALL LABOR.
OUR PROMISE.

3 YEAR WARRANTY
ALL OUTDOOR LAMINATED DIGITAL PRINTS
OUR PROMISE.

SIGN DETAILS
SCALE: ½" = 1'-0"

SIGNCOAMERICA
7938 WRIGHT RD • HOUSTON, TX 77041 • 713-661-1500
www.SigncoAmerica.com

CLIENT	MIRAMAR SHOPPING CENTER	**DRAWING**	SCA18 2545 O:\14-PROJECTS\M	**REVISIONS**	
ADDRESS	2000 HIGHWAY 146	**DESIGNER**	OUN	**R6**	4.15.2020 - ADD 3RD OPTION - OUN
CITY/ STATE	SEABROOK, TX 77586	**SALES REP**	GLORIA BAKER	**R7**	5.18.2020 - CHANGE SIZES, COLORS - OUN
DATE	5.22.19	**PROJECT MGR**	PATTY HICKS	**R8**	5.29.2020 - OPTION 2 = 31'

APPROVALS
CLIENT
LANDLORD
SALES REP

NEW CONSTRUCTION [Y|N] **PAGE 5**

SPECIFICATIONS ALL ELECTRIC SIGNS AND PRODUCTS MANUFACTURED BY SIGNCO AMERICA ARE BUILT ACCORDING TO **UL** STANDARDS

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

THIS DRAWING IS THE PROPERTY OF SIGNCOAMERICA, LP. ANY REPRODUCTION OR EXHIBITION OF THIS DRAWING IS STRICTLY PROHIBITED. © 2020 ALL RIGHTS RESERVED

SIGN A 31' – REJECTED



SIGN A 22' – PROPOSED



LETTER VISIBILITY CHART FOR HIGH IMPACT SIGNS

LETTER HEIGHT	READABLE DISTANCE FOR MAXIMUM IMPACE	MAXIMUM READABLE DISTANCE	APPROXIMATE TIME TO READ AT 45 MPH	APPROXIMATE TIME TO READ AT 60 MPH
3"	30'	100'	1.5 sec	1.1 sec
4"	40'	150'	2.2 sec	1.7 sec
6"	60'	200'	3.0 sec	2.3 sec
8"	80'	350'	5.3 sec	3.9 sec
9"	90'	400'	6.0 sec	4.5 sec
10"	100'	450'	6.8 sec	5.1 sec
12"	120'	525'	7.9 sec	5.9 sec
15"	150'	630'	9.5 sec	7.1 sec
18"	180'	750'	11.4 sec	8.5 sec
24	240'	1000'	15.1 sec	11.3 sec
30"	300'	1250'	18.9 sec	14.2 sec
36"	360'	1500'	22.7 sec	17.0 sec
42"	420'	1750'	26.5 sec	19.9 sec
48"	480'	2000'	30.3 sec	22.7 sec

This chart is based on using a bold black letter type such as Helvetica Bold
Some color combinations will vary the distance

SIGN A 12' – PER CODE



SIGN DETAILS
SCALE: ¼" = 1'-0"

SIGNCOAMERICA
7938 WRIGHT RD • HOUSTON, TX 77041 • 713-661-1500
www.SigncoAmerica.com

CLIENT	MIRAMAR SHOPPING CENTER	**DRAWING**	SCA18 2545 O:\14-PROJECTS\M	**REVISIONS**		**APPROVALS**	
ADDRESS	2000 HIGHWAY 146	**DESIGNER**	OUN	**R6**	4.15.2020 - ADD 3RD OPTION - OUN	**CLIENT**	
CITY/ STATE	SEABROOK, TX 77586	**SALES REP**	GLORIA BAKER	**R7**	5.18.2020 - CHANGE SIZES, COLORS - OUN	**LANDLORD**	
DATE	5.22.19	**PROJECT MGR**	PATTY HICKS	**R8**	5.29.2020 - OPTION 2 = 31'	**SALES REP**	

NEW CONSTRUCTION [Y|N] **PAGE 6**

SPECIFICATIONS ALL ELECTRIC SIGNS AND PRODUCTS MANUFACTURED BY SIGNCO AMERICA ARE BUILT ACCORDING TO **UL** STANDARDS

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

THIS DRAWING IS THE PROPERTY OF SIGNCOAMERICA, LP. ANY REPRODUCTION OR EXHIBITION OF THIS DRAWING IS STRICTLY PROHIBITED. © 2020 ALL RIGHTS RESERVED



N

SITE PLAN
SCALE: 1" = 70'-0"

SIGNCOAMERICA
7938 WRIGHT RD • HOUSTON, TX 77041 • 713-661-1500
www.SigncoAmerica.com

CLIENT	MIRAMAR SHOPPING CENTER	**DRAWING**	SCA18 2545 O:\14-PROJECTS\M	**REVISIONS**		**APPROVALS**	
ADDRESS	2000 HIGHWAY 146	**DESIGNER**	OUN	**R6**	4.15.2020 - ADD 3RD OPTION - OUN	**CLIENT**	
CITY/ STATE	SEABROOK, TX 77586	**SALES REP**	GLORIA BAKER	**R7**	5.18.2020 - CHANGE SIZES, COLORS - OUN	**LANDLORD**	
DATE	5.22.19	**PROJECT MGR**	PATTY HICKS	**R8**	5.29.2020 - OPTION 2 = 31'	**SALES REP**	

NEW CONSTRUCTION [Y|N] **PAGE 7**

SPECIFICATIONS ALL ELECTRIC SIGNS AND PRODUCTS MANUFACTURED BY SIGNCO AMERICA ARE BUILT ACCORDING TO **UL** STANDARDS

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

5 YEAR WARRANTY
ALL PARTS. ALL LABOR.
OUR PROMISE.

THIS DRAWING IS THE PROPERTY OF SIGNCOAMERICA, LP. ANY REPRODUCTION OR EXHIBITION OF THIS DRAWING IS STRICTLY PROHIBITED. © 2020 ALL RIGHTS RESERVED


PLAT OF SURVEY
BOUNDARY AND IMPROVEMENT
OF A 9.689 ACRE (422,070 SQ. FT.) TRACT
H.C.C.F. No. V052660
LOCATED IN
RITSON MORRIS SURVEY, A-52,
HARRIS COUNTY, TEXAS
Gruller Surveying, LLC
PROFESSIONAL LAND SURVEYING
5850 SAN FELIPE, SUITE 500, HOUSTON, TEXAS 77057
PHONE: (713) 333-1468 FAX: (713) 782-3755
SCALE: 1"=40'
FIELD BOOK-2016-JP
DATE:07-28-2016
G.F. No. NCS-760124-4-CHS2
ADDRESS: 2000 BAYPORT, SEABROOK, TX 77586
DWG. NO. 45-1660.dwg
I do hereby certify that this survey was this day made on the ground. This plat correctly represents the facts found at the time of the survey.
Terry L. Gruller
Texas Registered Professional Land Surveyor No. 5476
NOTES:
1. The surveyor has not abstracted the subject property.
2. Survey was created with the benefit of a title commitment prepared by First American Title Insurance Company, under G.F. No. NCS-760124-4-CHS2, dated July 20, 2016.
3. Basis of Bearings for the survey is the deed of record in H.C.C.F. Number V052660.
4. By graphic plotting only, the subject tract is located in Zone "X" shaded (Areas of 0.2% annual chance flood; areas of 1% annual chance flood with average depth less than one foot or with drainage areas less than one square mile) and Zone "AE", areas determined to be within the 1% annual chance flood, as scaled from Flood Insurance Rate Map No. 48201C1085G, dated June 18, 2007.
5. Subject to a perpetual, non-exclusive easement for automobile parking and automobile and pedestrian ingress and egress, and perpetual, non-exclusive easements for the purpose of installing, operating, maintaining, repairing and removing any and all utility lines and facilities, including surface drainage rights granted to McDonalds Corporation recorded under H.C.C.F. Number G810175
Schedule B
f. An utility easement ten (10) feet in width, together with an unobstructed aerial easement adjoining thereto five (5) feet wide from a plane twenty (20) feet above the ground upward, as set forth and defined in instrument recorded in Volume 5359, page 22, of the Deed Records of Harris County, Texas (same being filed for record under Harris County Clerk's File No. 8809810).
g. An utility easement five (5) feet in width along the most Easterly South property line(s), together with an unobstructed aerial easement adjoining thereto five (5) feet wide from a plane twenty (20) feet above the ground upward, as set forth and defined in instrument recorded in Volume 5359, Page 22, of the Deed Records of Harris County, Texas (same being filed for record under Harris County Clerk's File No. 8809810).
h. An Houston Lighting & Power Company guy easement(s) three (3) feet by three (3) feet in size, as set forth and defined in instrument recorded in Volume 5565, Page 218, of the Deed Records of Harris County, Texas (same being filed for record under Harris County Clerk's File No. 8907801).
i. An utility easement ten (10) feet in width, together with an unobstructed aerial easement adjoining thereto five (5) feet wide from a plane twenty (20) feet above the ground upward, as set forth and defined in instrument recorded in Volume 5586, Page 365, of the Deed Records of Harris County, Texas (same being filed for record under Harris County Clerk's File No. C070321).
j. Easement;
To: City of Seabrook
Recorded: Volume 5359, Page 22, City of Seabrook
Records, of Harris County, Texas.
Purpose: Water lines & sewer line facilities
k. Easement;
To: City of Seabrook
Recorded: Volume 5359, Page 22, City of Seabrook
Records, of Harris County, Texas.
Purpose: Water lines & sewer line facilities
l. A perpetual, non-exclusive easement for automobile parking and non-exclusive easements for the purpose of installing, operating, maintaining, repairing and removing any and all utility lines and facilities, including surface drainage rights granted to McDonalds Corporation recorded under H.C.C.F. Number G810175. (see note 5)
m. A Right-of-way easement 48.16 feet in width along the East property line(s), as set forth and defined in instrument filed for record under Harris County Clerk's File No. 9223582.
p. Terms, Conditions, and Stipulations in Short Form Lease;
Lessor: Seabrook Village, Ltd., a Texas limited partnership
Lessee: Family Dollar Stores of Texas, Inc., a Texas Corporation
Recorded: March 21, 2006 in County Clerk's File No. W086409, and as amended in County Clerk's File No. W086409, of the Official Public records, of Harris County, Texas.
Subordination, Non-Disturbance and Attornment Agreement:
Recorded: August 21, 2006 in County Clerk's File No. 2344078, of the Official Public Records of Harris County, Texas.
r. Terms, Conditions, and Stipulations in Short Form Lease;
Lessor: Seabrook Village, Ltd., a Texas limited partnership
Lessee: Burke's Outlet Stores-Tx, Inc., a Texas corporation
Recorded: March 21, 2006 in County Clerk's File No. Y483498, of the Official Public records, of Harris County, Texas.
Confirmation of Lease Term Agreement has recorded in June 11, 2002 under County Clerk's File No. Y863101, Official Public Records of Harris County, Texas.
Subordination, Non-Disturbance and Attornment Agreement:
Recorded: August 21, 2006 in County Clerk's File No. 2344076, of the Official Public Records of Harris County, Texas.
METES AND BOUNDS DESCRIPTION
9.689 ACRE TRACT
LOCATED IN THE
RITSON MORRIS SURVEY, A-52,
HARRIS COUNTY, TEXAS
Being a tract or parcel of land containing 9.689 acres of land or 422,070 square feet, located in the Ritson Morris Survey, Abstract 52, Harris County, Texas, being out of and a part of that certain 422.070 acre tract conveyed to Ohio United Liability Company in Harris County Clerk's File (H.C.C.F.) No. V052660, Official Public Records of Real Property of Harris County, Texas, said 9.689 acre tract being more particularly described as follows (all bearings based on said deed);
BEGINNING at a 1/2" inch iron pipe found for the northwest corner of the herein described tract, being the northwest corner of Lot 32, Block One, Seabrook Village Section One, an addition recorded in Volume 33, Page 1, Map Records of Harris County (H.C.M.R.), and on the south R.O.W. line of Hialeah Drive (60 feet wide);
THENCE, coincident the east line of the herein described tract and the west line of aforesaid Lot 32, South 07 Degrees 04 Minutes 00 Seconds East, a distance of 510.13 feet to a 5/8 inch iron rod found for the southeast corner of Lot 17 in aforesaid subdivision, being on the north R.O.W. line of Florida Street (60 feet wide);
THENCE, coincident the north R.O.W. line of aforesaid Florida Street, South 82 Degrees 56 Minutes 00 Seconds West, a distance of 46.10 feet to a 5/8 inch iron rod found for a point on the north R.O.W. line of said Florida Street and the northeast corner of Lot 2;
THENCE, coincident the west line of aforesaid Lot 2, South 07 Degrees 04 Minutes 00 Seconds East, a distance of 170.00 feet to a 5/8 inch iron rod found for the southeast corner of the herein described tract, being the northeast corner of Lot 1, a subdivision plat of record in Volume 87, Page 35, H.C.M.R., and the west R.O.W. line of said Bahama Drive;
THENCE, coincident the north line of aforesaid Lot 2, South 82 Degrees 56 Minutes 00 Seconds West, a distance of 130.00 feet to a 5/8 inch iron rod found for the northwest corner of said Lot 2;
THENCE, coincident the west line of aforesaid Lot 2, South 07 Degrees 04 Minutes 00 Seconds East, a distance of 150.00 feet to a 5/8 inch iron rod found for the southwest corner of the herein described tract, being the northwest corner of Lot 3, a subdivision plat of record in Volume 87, Page 35, H.C.M.R., and the west line of aforesaid Bahama Drive;
THENCE, coincident the south line of the herein described tract and the north line of aforesaid Lot 3, South 82 Degrees 56 Minutes 00 Seconds West, a distance of 463.12 feet to a 5/8 inch iron rod found for the southwest corner of the herein described tract, being the northwest corner of said Lot 3, and on the east R.O.W. line of El Mar Lane (80 feet wide);
THENCE, coincident the west line of the herein described tract and the east R.O.W. line of aforesaid El Mar Lane, North 07 Degrees 04 Minutes 00 Seconds West, a distance of 330.00 feet to a 5/8 inch iron rod found for the northwest corner of the herein described tract, being on the south R.O.W. line of aforesaid State Highway 146;
THENCE, coincident the south R.O.W. line of aforesaid State Highway 146, North 82 Degrees 56 Minutes 00 Seconds East, a distance of 463.12 feet to a 5/8 inch iron rod found for the northeast corner of the herein described tract, being the northwest corner of aforesaid Lot 2;
THENCE, coincident the west line of aforesaid Lot 2, South 07 Degrees 04 Minutes 00 Seconds East, a distance of 150.00 feet to a 5/8 inch iron rod found for the southwest corner of said Lot 2;
THENCE, coincident the north line of aforesaid Lot 2, North 82 Degrees 56 Minutes 00 Seconds East, a distance of 130.00 feet to a 5/8 inch iron rod found for the southeast corner of said Lot 2, and on the west R.O.W. line of aforesaid Bahama Drive;
THENCE, coincident the west R.O.W. line of aforesaid Bahama Drive, South 07 Degrees 04 Minutes 00 Seconds East, a distance of 170.00 feet to a 5/8 inch iron rod found for the northeast corner of aforesaid Lot 17, Block One, Seabrook Village Section One, an addition recorded in Volume 33, Page 1, Map Records of Harris County (H.C.M.R.), and on the south R.O.W. line of aforesaid Florida Street (60 feet wide);
THENCE, coincident the south R.O.W. line of aforesaid Florida Street, South 82 Degrees 56 Minutes 00 Seconds West, a distance of 510.13 feet to the POINT OF BEGINNING and containing 9.689 acres of land.
LEGEND
IRON ROD SET/FND
GUY ANCHOR
POST
SAMPLE WELL
GAS VALVE & BOX
GAS METER
WATER METER
ELECTRIC METER
CABLE EQUIPMENT
LIGHT STANDARD
TREE
TRAFFIC SIGN
POWER POLE
FIBER OPTIC CABLE
MANHOLE
IRRIGATION CONTROL VALVE
CURB INLET
AREA INLET
FIRE HYDRANT
F.D.C.
B.F.P.
TOP OF CURB ELEVATION
GUTTER ELEVATION
WOOD FENCE
CHAIN LINK FENCE
WROUGHT IRON FENCE
OVERHEAD ELECTRIC
WATERLINE
GAS LINE
TELEPHONE LINE
CABLE TV LINE
TOP OF BANK
+45.6 EXIST. NATURAL GROUND ELEVATION
+45.67 EXIST. ASPHALT OR CONCRETE ELEVATION
LINE DRAWING DISTANCE
L1 N 07°04'00" W 150.00'
HIALEAH DRIVE (60' R.O.W.) H.C.C.F. No. V723562
FLORIDA STREET (60' R.O.W.)
BAHAMA DRIVE (60' R.O.W.)
EL MAR LANE (80' R.O.W.)
STATE HIGHWAY 146 (120' R.O.W.)
9.689 ACRES (422,070 SQ. FT.) OHIO BLOCK MAP
PROPOSED 0.1762 ACRE R.O.W. TAKING PARCEL 123 PART ONE
PROPOSED 0.4456 ACRE R.O.W. TAKING PARCEL 123 PART TWO
0.6887 ACRE MCDONALD'S CORPORATION, H.C.C.F. No. G810175
0.5165 ACRE MCDONALD'S CORPORATION, H.C.C.F. No. P780419
PALMS ROYAL LEASE AREA
AREA WITHIN PALMS ROYAL LEASE=7,780 SQ. FT. AREA WITHIN PALMS ROYAL LEASE TO BE REMOVED TO ALLOW FOR R.O.W. TAKING=4,560 SQ. FT.
525'-3" ±
PYLON SIGN
PYLON SIGN
S82°56'00"E 510.13'
S07°04'00"E 170.00'
S82°56'00"W 130.00'
S07°04'00"E 130.00'
N07°04'00"W 200.00'
N82°56'00"E 150.00'
N07°04'00"W 150.00'
S82°56'00"E 150.00'
N07°04'00"W 330.00'
S82°56'00"W 463.12'
N82°56'00"E 471.28'
S82°56'00"E 46.10'
FND 5/8" I.R.
FND CROW'S FOOT
SET 5/8" I.R. W/ CAP STAMPED "GRUL"
SET CROW'S FOOT
P.O.B.
P.O.C.
49.167 50. FT. RIGHT-OF-WAY ESMT. H.C.C.F. No. K725561
10' U.E. & 5' W.L.E. FACILITIES H.C.C.F. No. E445589
10' U.E. & 5' W.L.E. VOL. 5359, PG. 22, H.C.D.R.


AMENDING PLAT
MIRAMAR SHOPPING CENTER
BEING A SUBDIVISION OF 9.4839 ACRES
LOCATED IN THE
RITSON MORRIS SURVEY, A-52,
CITY OF SEABROOK
HARRIS COUNTY, TEXAS
SCALE: 1" = 50'
JANUARY 2019
1 RESERVE
1 BLOCK
OWNER:
Miramar Bethline GP, LLC
2000 HIGHWAY 146
SEABROOK, TX 77586
Phone: (214) 352-0411
Gruller Surveying, LLC
PROFESSIONAL LAND SURVEYING
5599 SAN FELIPE, STE. 1400
HOUSTON, TEXAS 77056
PH:713.850.1010 FAX:713.850.1330
JOB NO. 18-1680
RP-2019-39101
1/30/2019 HCPRPF2 60.00
FILED
12:41 PM
1/30/2019
COUNTY CLERK
NOTES:
1. This plat is in conformance with the City of Seabrook's comprehensive Ordinance which are not shown on the plat. If the comprehensive Zoning the filed plat, the more stringent conditions shall apply.
This plat was created with the benefit of a City Planning Letter prepared by Integrity Title, Job No. 1629250A, effective Date: June 25, 2018
3. Coordinates shown hereon are Texas State Plane Coordinate System, NAD 83, Texas South Central Zone. Easements and building setback lines shown hereon are recorded in the Harris County Clerk's File No. E445588 unless otherwise noted.
4. By graphic plotting only, the subject tract is located in Zone "AE", areas Federal Emergency Management Agency Flood Insurance Rate Map No. 48201C0530L, dated January 6, 2017.
5. Subject to a non-exclusive perpetual easement for automobile parking and pedestrian ingress and egress, and non-exclusive easements for the purpose of installing, operating, maintaining, repairing and replacing public utility lines and related facilities, including surface drainage rights granted to McDonalds Corporation, recorded under Harris County Clerk's File No. E445587.
6. Drainage easements shall be kept clear of buildings, pools, and other obstructions to the operations and maintenance of the drainage facility. Eaves may encroach no more than 18 inches into any easement.
7. Subject to Declaration of Easement, Covenants and Restrictions recorded under Harris County Clerk's File No. E445588.
VICINITY MAP
SCALE: NTS
SUBJECT TRACT
SEABROOK
SOUTHERN PACIFIC
GALVESTON BAY
TEXAS
R.O.W.
BLOCK 1
RESTRICTED RESERVE "A"
(RESTRICTED TO COMMERCIAL USE ONLY)
9.4839 ACRES
(413,123 SQ. FT.)
HILLARD DRIVE
(80' R.O.W.)
VOL. 87, PG. 35, H.C.M.R.
EL MAR LANE
(80' R.O.W.)
VOL. 87, PG. 35, H.C.M.R.
FLORIDA STREET
(R.O.W. VARIES)
F.C. No. 381056
BAHAMA DRIVE
(60' R.O.W.)
VOL. 87, PG. 35, H.C.M.R.
STATE HIGHWAY 146
(R.O.W. VARIES)
TXDOT CSJ #0912-33-097
TXDOT CSJ #0912-33-098
RP-2018-365556
RESTRICTED RESERVE "B"
MIRAMAR SECTION
VOL. 87, PG. 35, H.C.M.R.
LOT 1
LOT 2
LOT 3
LOT 4
LOT 5
LOT 6
LOT 7
LOT 8
LOT 9
LOT 10
LOT 11
LOT 12
LOT 13
LOT 14
LOT 15
LOT 16
LOT 17
LOT 18
LOT 19
LOT 20
LOT 21
LOT 22
LOT 23
LOT 24
LOT 25
LOT 26
LOT 27
LOT 28
LOT 29
LOT 30
LOT 31
LOT 32
P.O.B.
N: 13779341.43
E: 3231569.31
FND. 5/8" I.R. UNLESS OTHERWISE NOTED
S10°08'46"E 510.13'
S10°08'46"E 170.00'
S10°08'46"E 130.00'
S79°51'14"W 404.35'
N79°51'14"E 551.88'
N10°08'46"W 150.00'
S79°51'14"W 150.00'
N10°06'50"W 325.50'
N10°06'45"W 330.00'
L1
L2
49.187 SQ. FT. RIGHT-OF-WAY DEDICATION
H.C.C.F. No. K732582
15' W.E.& SEW. FACILITIES H.C.C.F. No. E445587
10' U.E. (BLANKET)
10' U.E. (BLANKET)
10' U.E. (BLANKET)

MIRAMAR SHOPPING CENTER

SEABROOK, TEXAS

SIZE

93,691 square feet

MAJOR TENANTS

Palais Royal

Burke's Outlet

Tuesday Morning

LOCATION

2000-2100 St Highway 146 | Seabrook, Texas 77586

PROPERTY HIGHLIGHTS

- 93,691 sf with Palais Royal, Burke's Outlet, Tuesday Morning, Sherwin Williams and Blockbuster
- Excellent location on S.R. 146 (Bayport Blvd), 15 miles southeast of Houston
- Population exceeds 80,200 in a five-mile trade area with average household income over $100,600

SIGNCOAMERICA

7938 WRIGHT RD • HOUSTON, TX 77041 • 713-661-1500

www.SigncoAmerica.com

CLIENT	MIRAMAR SHOPPING CENTER	**DRAWING**	SCA18 2545 O:\14-PROJECTS\M	**REVISIONS**		**APPROVALS**	
ADDRESS	2000 HIGHWAY 146	**DESIGNER**	OUN	**R6**	4.15.2020 - ADD 3RD OPTION - OUN	**CLIENT**	
CITY/ STATE	SEABROOK, TX 77586	**SALES REP**	GLORIA BAKER	**R7**	5.18.2020 - CHANGE SIZES, COLORS - OUN	**LANDLORD**	
DATE	5.22.19	**PROJECT MGR**	PATTY HICKS	**R8**	5.29.2020 - OPTION 2 = 31'	**SALES REP**	

SPECIFICATIONS ALL ELECTRIC SIGNS AND PRODUCTS MANUFACTURED BY SIGNCO AMERICA ARE BUILT ACCORDING TO **UL** STANDARDS

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

THIS DRAWING IS THE PROPERTY OF SIGNCOAMERICA, LP. ANY REPRODUCTION OR EXHIBITION OF THIS DRAWING IS STRICTLY PROHIBITED. © 2020 ALL RIGHTS RESERVED

MIRAMAR SHOPPING CENTER

2000-2100 STATE HWY 146 | SEABROOK, TX 77586

5 YEAR WARRANTY
ALL PARTS. ALL LABOR.
OUR PROMISE.

SPACE	TENANT	SQ. FT.
10	Seabrook Trophy & Awards	4,069
40	Beacon Federal Credit Union	2,400
50	PT Nails	1,200
60	Leased **AVAILABLE**	1,208
70	Hi-Tech Cuts	1,188
80	Burkes Outlet	15,967
100	Tuesday Morning	8,460
120	Allcar Insurance Agency	766
130	Edward Jones	1,588
150	Kids Workshop	2,392
160	Mama Bella's Beauty Salon	1,208
170	Cricket	1,208
180	Sherwin Williams	3,972
190	Family Dollar	9,000
200	Tiger's Den	7,000
210	Stage Stores	22,000
220	Pizza Hut	1,666
230	Jackson Hewitt	2,500
O-1	Rustic Design Company (Temp)	5,500
TOTAL SQ. FT.		93,292

SITE LEGEND

- **Available**
- **Occupied**
- **Leased (not occupied)**
- **Owned by Others**

SITE PLAN
NOT TO SCALE

SIGNCOAMERICA
7938 WRIGHT RD • HOUSTON, TX 77041 • 713-661-1500
www.SigncoAmerica.com

CLIENT	MIRAMAR SHOPPING CENTER	**DRAWING**	SCA18 2545 O:\14-PROJECTS\M	**REVISIONS**	
ADDRESS	2000 HIGHWAY 146	**DESIGNER**	OUN	**R6**	4.15.2020 - ADD 3RD OPTION - OUN
CITY/ STATE	SEABROOK, TX 77586	**SALES REP**	GLORIA BAKER	**R7**	5.18.2020 - CHANGE SIZES, COLORS - OUN
DATE	5.22.19	**PROJECT MGR**	PATTY HICKS	**R8**	5.29.2020 - OPTION 2 = 31'

APPROVALS
CLIENT
LANDLORD
SALES REP

SPECIFICATIONS ALL ELECTRIC SIGNS AND PRODUCTS MANUFACTURED BY SIGNCO AMERICA ARE BUILT ACCORDING TO **UL** STANDARDS

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

THIS DRAWING IS THE PROPERTY OF SIGNCOAMERICA, LP. ANY REPRODUCTION OR EXHIBITION OF THIS DRAWING IS STRICTLY PROHIBITED. © 2020 ALL RIGHTS RESERVED

5 YEAR WARRANTY
ALL PARTS. ALL LABOR.
OUR PROMISE.

Shopping Center consists of internally illuminated Flush mount (for anchor tenants) and Raceway mounted channel letters throughout.

Raceways are painted the color of the facade to hide the mounting but protect the building.

SIGNCOAMERICA
7938 WRIGHT RD • HOUSTON, TX 77041 • 713-661-1500
www.SigncoAmerica.com

CLIENT	MIRAMAR SHOPPING CENTER	**DRAWING**	SCA18 2545 O:\14-PROJECTS\M	**REVISIONS**		**APPROVALS**	
ADDRESS	2000 HIGHWAY 146	**DESIGNER**	OUN	**R6**	4.15.2020 - ADD 3RD OPTION - OUN	**CLIENT**	
CITY/ STATE	SEABROOK, TX 77586	**SALES REP**	GLORIA BAKER	**R7**	5.18.2020 - CHANGE SIZES, COLORS - OUN	**LANDLORD**	
DATE	5.22.19	**PROJECT MGR**	PATTY HICKS	**R8**	5.29.2020 - OPTION 2 = 31'	**SALES REP**	

SPECIFICATIONS ALL ELECTRIC SIGNS AND PRODUCTS MANUFACTURED BY SIGNCO AMERICA ARE BUILT ACCORDING TO **UL** STANDARDS

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

THIS DRAWING IS THE PROPERTY OF SIGNCOAMERICA, LP. ANY REPRODUCTION OR EXHIBITION OF THIS DRAWING IS STRICTLY PROHIBITED. © 2020 ALL RIGHTS RESERVED

EXHIBIT C
SIGN CRITERIA

SECTION I.
The advertising or informative content of all signs shall be limited to letters designating the store name and/or type of store (any such designation of the store type shall be by general descriptive terms and shall not include any specifications of the merchandise offered for sale therein or the services rendered therein) only and shall contain no advertising devices, slogans, symbols or marks (other than the store name and/or type of store). Crests and corporate shield designs are not permitted.

SECTION II.
Landlord will provide an area on the sign band or canopy of appropriate size and location to Tenant's storefront. After having first obtained Landlord's written approval of Tenant's sign design, prepared in accordance with this criteria, Tenant will properly install a sign face in the sign band. The letter style on all signs shall be shown on drawings submitted to Landlord for approval.

SECTION III.
The character, design, color and layout of all signs shall be subject to Landlord's prior approval.

SECTION IV.
Excepting the signs specified in Section VI (d) and (e) of this exhibit, no occupant shall install more than one (1) sign.

SECTION V.
All signs shall be in accordance with the following requirements:
(a) The sign lettering or any part thereof shall be located within the physical limits of the storefront of the Demised Premises and must remain at least eighteen (18") inches away from the lease lines where they meet the sign band.
(b) Except for those signs mounted on the mansards with Landlord's written approval, no sign or any part thereof shall be located on the roof of the Demised Premises.
(c) Sign style and lettering must be approved by Landlord before shop drawings are made once initial approval is given by Landlord. Tenant shall then submit shop drawings for final Landlord approval, showing the sizes of all letters and spacing, type of material, color and dimensions in relation to leasable area.
(d) No sign will be placed in final position without the written approval of Landlord. The general standard is that the top plane of the sign shall be in line with the other Tenant signage.
(e) Tenant's sign shall be individually-lettered, channel-lighted, and mounted on a raceway.
(f) All signs shall be fabricated and installed in compliance with all applicable codes.

SECTION VI.
The fabrication, installation and operation of all signs shall be subject to the following restrictions:
(a) All storefront signs must be internally illuminated and regulated by a timer or photo cell.
(b) No flashing, moving, flickering or blinking illumination shall be permitted.
(c) No animation, moving lights or floodlight illumination shall be permitted.
(d) No painted or printed signs, except one (1) non-illuminated, small scale "Signature Sign" or "store hours" sign, which is lettered on the glass portion of the store of an occupant, provided such sign does not exceed three inches (3") in height. Also permitted are small credit card symbols.
(e) No outrigger signs, except one (1) identification sign located beneath the canopy in a location to be designated by Landlord, and in accordance with Landlord's criteria for undercanopy signs. Tenant must submit drawing of said sign to Landlord and obtain Landlord's written approval prior to installation of this, or any sign.
(f) No moving signs, rooftop signs, parapet signs, exposed neon or pylon signs.

SECTION VII.
At such time as Landlord prepares a new sign design plan for the Shopping Center, Tenant will remove its existing sign and install a new one to comply with such new plan at Tenant's sole expense.

If Landlord undertakes a shopping center renovation that requires removal of Tenant's signs, Tenant shall be responsible for removal and reinstallation of signs. Tenant may be required to update older signage to meet new sign criteria at no cost to Landlord.

SIGN CRITERIA

The purpose of this Sign Criteria is to create a graphic environment that is individual and distinctive in identity for the Tenant and compatible with other signs in the center. The total concept should give an impression of quality, professionalism and install a good business image.

The following specifications are to be used for the design of your sign; however, in all cases, final written approval must be obtained from the Lessor prior to the manufacturing or installation of any signage. Lessor shall make final and controlling determinations concerning any questions of this sign policy.

NOTICE: Written approval and conformation with these specifications does not imply conformance with local City or County sign ordinances.

A. REQUIRED SIGNS
   1. Tenant shall erect one (1) sign which shall be attached directly to the building fascia as described hereinafter. Where the Leased Premises is an endcap, the Tenant may install a fascia sign on front and side elevations.
B. TYPE OF SIGN
   1. Internally illuminated acrylic faced, individual to the building. Mounting hardware shall be non-corrosive and neatly concealed from public view.
C. SIZE OF SIGN
   1. Depth – 5"- 7"
   2. Height: Single Row – not to exceed 36"; Multiple Rows – not to exceed 48" in total height including spaces between rows; Minimum letter size – 12".
   3. The overall length or spread of letters cannot exceed 80% of the total linear storefront measurement of the leased space. Example: 60' frontage, maximum size – 48'0".
   4.
D. TYPE OF SIGN
   1. Any style (block or script) may be used. Upper and lower-case letters allowed.
   2. Subject to approval Tenant may use pictorial logos and symbols. They must be proportionate to height of fascia and sign.
   3. Box type signs not permitted
E. COLOR OF LETTERS
   1. Faces to be 3/16" acrylic – colors to be approved on case by case.
   2. #313 Dk. Bronze 1" trim and returns
F. COLOR OF RACEWAYS: Painted to match the building (provide paint color)

G. CONSTRUCTION OF LETTERS

5 YEAR WARRANTY
ALL PARTS. ALL LABOR.
OUR PROMISE.

Miramar S/C
SIGN CRITERIA
These design guidelines have been created to keep the uniformity and overall design of the center

BUILDING SIGNS
FACE-LIT CHANNEL LETTERS
TENANT REQUIREMENTS
- Signs must comply with allowances according to City of Seabrook Permitting Department.
- Signs must be fabricated and installed by a licensed manufacturer.
- No sign shall be installed without first obtaining Landlord's written approval of signage plans conforming to the following criteria. Submit (2) copies of drawings to Landlord for approval.

DESIGN REQUIREMENTS
- Sign must include tenant's name. Logos are allowed. Subject to Landlord's approval
- Type of Sign: FACE-LIT – Raceway mounted & Flush mount
  Channel Letter Fabrication:
  - Faces to be 3/16" acrylic
  - Returns to be .040 aluminum painted dk. bronze
  - 1" Jewelite trim - bronze
  - Letter depth to be 5"
  - Backs to be .063 aluminum
  - Internal illumination to be 3000K bright white LEDs

- Sign Height Limitations:
  - Single Line: No letter shall be less than 12" nor more than 48"
  - Double Line: No letter shall be less than 12" and overall height nor more than 48 "
  - Maximum span of the tenant sign shall not exceed 80% of the store frontage
- All type must be centered horizontally in the sign band portion corresponding to each tenant. Each line (or double line) must also be centered vertically within the sign band area designated by Landlord. Landlord reserves the right to designate the horizontal location of tenant's signage in a manner so as not to be centered in front of the tenant's demised premises.

CONSTRUCTION REQUIREMENTS
- All signs, bolts, fastenings, and clips shall be aluminum.
- All penetrations of the building structure required for sign installation shall be neatly sealed in a watertight condition. All mounting hardware shall be non-corrosive and neatly concealed from public view.
- Tenant shall be fully responsible for the actions of and payments to tenant's sign contractor.

PYLON SIGNS
TENANT REQUIREMENTS
- Signs must comply with allowances according to City of Seabrook Permitting Department.
- Signs must be fabricated and installed by a licensed manufacturer.
- No sign shall be installed without first obtaining Landlord's written approval of signage plans conforming to the following criteria. Submit (2) copies of drawings to Landlord for approval.
- Tenant shall be fully responsible for the actions of and payments to tenant's sign contractor.

DESIGN and CONSTRUCTION REQUIREMENTS
- Sign must include tenant's name AND ANY LOGOS are allowed.
- *All graphics/lettering to be translucent vinyl and must be approved by Landlord.*
- *Type of Sign: Internally illuminated double-sided pylon sign with tenant panels*

SIGNCOAMERICA
7938 WRIGHT RD • HOUSTON, TX 77041 • 713-661-1500
www.SigncoAmerica.com

CLIENT	MIRAMAR SHOPPING CENTER	**DRAWING**	SCA18 2545 O:\14-PROJECTS\M	**REVISIONS**		**APPROVALS**	
ADDRESS	2000 HIGHWAY 146	**DESIGNER**	OUN	**R6**	4.15.2020 - ADD 3RD OPTION - OUN	**CLIENT**	
CITY/ STATE	SEABROOK, TX 77586	**SALES REP**	GLORIA BAKER	**R7**	5.18.2020 - CHANGE SIZES, COLORS - OUN	**LANDLORD**	
DATE	5.22.19	**PROJECT MGR**	PATTY HICKS	**R8**	5.29.2020 - OPTION 2 = 31'	**SALES REP**	

SPECIFICATIONS ALL ELECTRIC SIGNS AND PRODUCTS MANUFACTURED BY SIGNCO AMERICA ARE BUILT ACCORDING TO **UL** STANDARDS

THIS SIGN IS INTENDED TO BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF ARTICLE 600 OF THE NATIONAL ELECTRICAL CODE AND/OR OTHER APPLICABLE LOCAL CODES. THIS INCLUDES PROPER GROUNDING AND BONDING OF THE SIGN.

THIS DRAWING IS THE PROPERTY OF SIGNCOAMERICA, LP. ANY REPRODUCTION OR EXHIBITION OF THIS DRAWING IS STRICTLY PROHIBITED. © 2020 ALL RIGHTS RESERVED